



November 29, 2016

Project Summary: Demolition
1242 Hewitt Avenue
St Paul, MN 55104

11/29 – 12/19/2016: Apply for permits. Have house baited for rodents. Notify to have gas and electric disconnected. Asbestos testing. Send notifications out to neighbors about the demolition of the house

12/20 – 12/27/2016: Install silt fence for erosion control. Demolish residence (1,504 SF) and garage / disposal of materials off site in accordance with local, state and federal regulations. Rough grade disturbed areas to existing contours (Please note we will be unable to backfill and hydro seed until the weather breaks in March / April of 2017).

12/27 – 01/06/2017: Inspections. We will be unable to finalize the results until the backfill and hydro seed has been completed.

April, 2017 – Backfill soil and hydro seed where disturbed

Amount Due upon completion of demolition: \$29,200.00

Amount Due upon completion of Backfill and hydro seed: \$ 1,425.00

Any alteration from the above specifications and corresponding pricing agreement will be made only at the customer's request or approval. Completing the work in this proposal at the time scheduled is contingent upon accidents or delays beyond our control.

Authorized signature Cindy Swick Date 12/5/16
Title Cyprex Services / NATIONAL Repairs Mgr

Acceptance of contract – We are aware of and agree to the contents of this proposal. You are authorized to do the work as specified in the proposal. We will make the payment set forth in this contract at the time it is due.

Client signature Susan A. Wink Date 12-5-16
Title AUP / US Bank





December 5, 2016

Project Summary: Asbestos Abatement
1242 Hewitt Avenue
St Paul, MN 55104

Asbestos testing results have confirmed that the following areas will need abatement:

- Basement (gray floor tile)
- Kitchen (red floor tile)
- 2nd floor bathroom (cream gray flooring)
- 2nd floor (white window glazing)
- Basement (off white flue packing)
- Basement (residue on pipe elbows)

Proposal: Remove identified asbestos containing material prior to demolition.

Amount due upon the completion of the asbestos abatement: \$4,665.00

Any alteration from the above specifications and corresponding pricing agreement will be made only at the customer's request or approval. Completing the work in this proposal at the time scheduled is contingent upon accidents or delays beyond our control.

Authorized signature

Cindy Brock

Date *12/5/16*

Title

Cyprex Services NATIONAL REPAIRS Mgr

Acceptance of contract – We are aware of and agree to the contents of this proposal. You are authorized to do the work as specified in the proposal. We will make the payment set forth in this contract at the time it is due.

Client signature

Susan Q. Wink

Date *12-5-16*

Title

AUP US Bank

