



- NOTES**
- GENERAL:**
- 1) Contractors and sub-contractors are to visit the site prior to issuing proposals.
 - 2) All contractors or, sub-contractors are to clean-up their areas at the end of each working day. The general contractor will, at the sub-contractors expense, clean any area not cleaned by the sub-contractors.
 - 3) All work is to be done in accordance with State, Local and ADA codes.
 - 4) Any contractor making penetrations into rated wall systems (i.e. corridor walls) are required to patch and fire caulk those penetrations.
- DEMOLITION:**
- 1) Remove concrete wall and curb.
- CONCRETE WORK:**
- 1) Cut and remove concrete wall for new door. Install frame.
 - 2) Cut and remove concrete curb-level at doorway.
 - 3) Level concrete to allow for exiting.
- LUMBER:**
- 1) furnish plywood for temporary enclosure.
- HARDWARE:**
- 1) Furnish frame, door and hardware as shown.
- ELECTRICAL:**
- 1) Install exit and emergency lighting as per code.
- CARPENTRY:**
- 1) Install door and hardware as shown.
- PAINTING:**
- 1) Paint new door and frame.

Spine Tree
 C E N T R E
 1600 UNIVERSITY AVENUE ST. PAUL, MINNESOTA 55104

RAMP RENEVATIONS
ALTERNATE #4

PROJECT NO.
 DRAWN BY: R.A. BANET
 DATE: 3/14/13

REVISIONS:

SHEET NO.
A1