



PROPOSAL

McCarthy Builders & Remodelers Inc.
 1291 Windcrest Ave
 St. Paul, MN 55123-1438
 Cell 612-250-0816 Fax 952-960-0085
www.McCarthybuildersandRemodelers.com

Date 1/15/2014

TO: Catholic Charities
 Mor Vue
 651-647-3199
Mor.Vue@cctwincities.org

RE: Dwight Freshwater
 263 Cliff St.
 St. Paul, MN 55102
 Contact - Sabian 651-225-0716
sabean58@yahoo.com

Description	HOUR	AMOUNT
Bathroom Modification		
Demo Remove(toilet, sink, drop ceiling, wains coating, floor ext..) Save toilet for re installation		
Demo Sub floor in new shower area & open wall		
Rough Plumbing New locations (toilet, sink, shower floor drain)		
Framing For new Shower (46 x 54) & pocket door.		
Plumbing Water line to new location (anti scald shower valve)		
Floor tile Continues tile sloping towards shower drain(40 sq ft)		
Sheet Rock Shower area, ceiling, pocket door area skim coat		
Wall Tile In shower area 7 feet in height (approx 120 Sq ft)		
Shower Valve Anti Scalding shower valve on slide bar		
Wall Sink In shower area		
Install Reinstall previous toilet		
Shower Curtain Shower Curtain and bar (full length)		
Electrical Install bath fan, heat Lamp & Recessed shower light		
Electrical Demo outlet in bedroom		
Ceiling Frame for sheet rock		
HVAC Relocate heat return in bedroom		
Install Pocket door		
Finishes Rock, paint stain as necessary.		
Pull Permits		
Remove Debris		
<i>Thank you for the opportunity</i>		
		\$ 21,975.00