Last Modified: 06/20/2022

ESTIMATE

T-10 Construction
14657 Helium Street NW
Ramsey, MN 55303
info@t10construction.com
(612) 254-8060

For: Jenny Louismet
Job Address: 132 Western Avenue South
Saint Paul, MN 55102
Jenny@dogsdigwalking.com
(651) 734-3464

Job Id 2206-3533679-01	Estimate # 0068	Estimate Date 06/20/2022	Estimate Amount	$25,350.00

#	Type	Name	(Price / Unit) x Qty	Line Total
1	ACTIVITY	House Roof	($17,250.00 / 1) x 1.00	$17,250.00
	Trade Type: ROOFING Work Type: Steep slope			
	Description: Remove and Replace existing Roof on House. Replace all underlayment (Ice and Water & 100# Felt) and Venting. Replace all Shingles. Using Atlas Pinnacle, Color TBD.			
2	ACTIVITY	Garage Roof	($7,350.00 / 1) x 1.00	$7,350.00
	Trade Type: ROOFING			
	Description: Remove/Replace and Re-deck Roof. Replace all underlayment (100# Felt). Re-deck all necessary areas. Replace Shingles using Atlas Pinnacle. Color=TBD			
3	ACTIVITY	Dumpster/Permit	($750.00 / 1) x 1.00	$750.00
	Description: Dumpster/Permit			

Total **$25,350.00**