

Dayana Valmyr			Estimate							
Phone number	651-428-4811									
Adress	1220 Sherburne Ave, Saint paul									
Email	Dayana.valmyr@lpmn.com									
place	work/material	comments	size	area	uom	quantity	color	price \$	total price \$	
outside work	work									
Replace exterior trim on windows	window type 1	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	33 3/4 x45" (58")	around	piec	11	old paint test			
	window type 2	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	44 x45" (58")	around	piec	28	old paint test			
	window type 3	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	86 1/4 x45" (58")	around	piec	5	old paint test			
	window type 4	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	56 x45" (58")	around	piec	16	old paint test			
	Fascia repair (front yard)	- fascia removal - installation of new fascia - silicone - painting	12x140"	front	piec	1	old paint test			
	Large window at the entrance	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting		front/back	piec	2	old paint test			
								Work total	13890	
	materials									
	Trim		538 Lf					1,98/l	1065,24	
	Flat Trim	- center of window (large size)	80 Lf					1,47/l	117,6	
	Ground Contact Pressure-Treated Southern Yellow Pine Lumber	2 in. x 6 in. x 8 ft.	250 Lf		piec	32		5,98	191,36	
	Flashing Tape				piec	3		35	105	
	screws / nails							70	70	
	Fascia		1x12'					45	45	
	Blu tape				piec	5				
	Foam	Window and Door Insulating Spray Foam Sealant			piec	3		17	51	
	Silicone	All Purpose Waterproof Sealant (12-Pack)			piec	12			179,5	
	Dap	White Premium Molding and Trim Sealant			piec	10		5,78	57,8	
	extra materials								220	
	Paint				gal	3	old paint test	52	156	
	Painting kit				piec	3		18	54	
	delivery of materials (purchases)								120	
	Scaffold Set Rental	3 weeks						250\$/week	750	
								materials total	3182,5	
								Total	17,072 \$	