

Dayana Valmyr			Estimate						
Phone number	651-428-4811								
Adress	1220 Sherburne Ave, Saint paul								
Email	Dayana.valmyr@lpmn.com								
place	work/material	comments	size	area	uom	quantity	color	price \$	total price \$
outside work	work								
Replace exterior trim on windows	window type 1	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	33 3/4 x45" (58")	around	piec	11	old paint test		
	window type 2	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	44 x45" (58")	around	piec	28	old paint test		
	window type 3	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	86 1/4 x45" (58")	around	piec	5	old paint test		
	window type 4	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting	56 x45" (58")	around	piec	16	old paint test		
	Fascia repair (front yard)	- fascia removal - installation of new fascia - silicone - painting	12x140"	front	piec	1	old paint test		
	Large window at the entrance	-removal of trim - cleaning of old silicone - insulation with foam - personalized installation of new trim - silicone (trim/bricks) - painting		front/back	piec	2	old paint test		
								Work total	13890
	materials								
	Trim		538 Lf					1,98/f	1065,24
	Flat Trim	- center of window (large size)	80 Lf					1,47/f	117,6
	Ground Contact Pressure-Treated Southern Yellow Pine Lumber	2 in. x 6 in. x 8 ft.	250 Lf		piec	32		5,98	191,36
	Flashing Tape				piec	3		35	105
	screws / nails							70	70
	Fascia		1x12'					45	45
	Blu tape				piec	5			
	Foam	Window and Door Insulating Spray Foam Sealant			piec	3		17	51
	Silicone	All Purpose Waterproof Sealant (12-Pack)			piec	12			179,5
	Dap	White Premium Molding and Trim Sealant			piec	10		5,78	57,8
	extra materials								220
	Paint				gal	3	old paint test	52	156
	Painting kit				piec	3		18	54
	delivery of materials (purchases)								120
	Scaffold Set Rental	3 weeks						250\$/week	750
								materials total	3182,5
								Total	17,072 \$